

**TATA MEMORIAL CENTER, ACTREC.**

Tender No.

TMC/ACTREC/ENGG/SPM/ET-24/Face lifting in Hadron/2021

23/07/2021

**Sub:** Face lifting works for all three Treatment Control Rooms, Patient Treatment Rooms (Gantry) and entrance maze in Proton Therapy Centre at ACTREC, Kharghar

**Schedule of Quantities.**

Name of Agency						
FINANCIAL BID						
Sr.No.	Description	HSN/SAC code	Qty.	Unit	Rate	Amount
1	Providing and fixing 1/2" approved colour composite marble with backing material on wall surface. Composite marble shall be of CMC or Asian Granito make OR any other Equivalent complete in all respect including cut out for switches, moulding etc. (Basic Rate Rs. 165 /170Sq.Ft.)		405.00	sqm.		-
2	Providing and fixing moulded composite marble photo frame over existing door frame & wooden partition complete in all respect as per drg & instructions.		18.00	Nos.		-
3	Providing and fixing composite marble moulding to be fix on wall as per drg & instruction.		225.00	Rmt.		-
4	Providing and fixing 1/2" thick composite marble over wooden partition, with special adhesive backing material complete in all respect.		36.00	sqm.		-
5	Providing and fixing wooden partition to be made by 2" X 1 1/2" thick wood section with both side 1/2" thick ply with one side finished with approved shade P.U laminated paint.		15.00	sqm.		-
6	Providing and fixing wooden panelling as shown in the Drg. panelling shall have 1" thick Block Board (horizontal & vertical) & 5" in depth to cover the existing electrical pipes panelling shall have 3/4" thick for openable shutter & 1/2" ply for fix portion as per drg. cut out to made in the panelling as per required. Panelling to be finished approved shade P.U. laminated paint. (Contractor should show one finished sample for approval) shutter out side P.U. finish & inside enamel paint, shutters shall have 3/4" X 1" solid wooden section to open the shutters as per details)		78.00	sqm.		-
7	Providing and fixing 1'-0" ht. box unit above panelling to cover all the conduit pipes. Box unit to be made in 3/4" thick marine ply with openable shutter & to be finished in P.U. laminated paint. Shutters shall have T.W. lipping all sides with shutter to open upwards hydraulic fitting Complete in all respect.		27.00	sqm.		-
8	Panelling same as Item F only change panelling shall have T.W. Frame out of 3" X 1 1/2" instead of 1" Block board frame work.		96.00	sqm.		-
9	Providing and fixing approved colour shell finish laminate to be fix, over existing doors by removing the existing laminate on both sides of the door complete in all respect. Door Size 6'-0" X 7'-6"		9.00	Nos.		-
10	Providing and fixing approved colour shell finish laminate to be fix, over existing doors by removing the existing laminate on both sides of the door complete in all respect. Door Size 3'-6" X 7'-6"		6.00	Nos.		-
11	Providing and fixing 12mm. thick Dupont corian of approved shade to be fixed over existing ply. Dupont to be fixed with adhesive, silicon tape etc. complete with cutting as required etc. Complete in all respect.		39.00	sqm.		-
12	Providing and fixing 4'-0" X 1'-6" wooden box to be fixed on wall for wash basin counter. Counter to be finished in all side in 1/2" DuPont corian material. Wooden box to be fix on bracket Complete in all respect with cut outs, polishing etc.		24	Rmt.		-
13	Providing and fixing 1" thick & 1'-6" wide Block board with laminated finish on floor as shown in the drg.		60.00	sqm.		-
14	Providing and fixing 2mm.thick Vinyl floor Roll form with self levelling on existing epoxy floor complete with wastage etc.including scratching or roughing the surface before fixing. vinyl floor make should be Tarket, Poly floor, Armstrong, forbo or any other Equivalent approved make.		276	sqm.		-
15	Providing & applying Luster paint in 3 coats on wall of approved shade.		90	sqm.		-
16	Providing & applying P.O.P Punning on wall to get smooth surface.		90	sqm.		-
17	Removing existing wash basin of any size & colour with all fittings & handing over the same with all fittings at required place to the department as directed by Engineer-In-Charge etc.complete.		3.00	Nos.		-
18	Providing and Fixing approved make square shape wash basin 18" X 1'-4" to be fixed on Dupont finished counter. (Kohler Make W.B.)		3.00	Nos.		-
19	Providing and Fixing Jaguar make mixture pillar cock to be fixed on wall		3.00	Nos.		-
20	Providing and Fixing Jaguar make Bottle trap		3.00	Nos.		-
21	Providing and fixing hafele make lipping to cover the joint in vinyal floor		45.00	Rmt.		-
22	Providing and fixing Graphic Panel Printed on vinyl paper		60.00	sqm.		-
23	Providing and fixing Door Handle 3'-0" Ht.in sets Good quality		24.00	Nos.		-
24	Providing & fixing Storage 1'-4" in depth X 2'-6" Ht. below Dupont finished counter. Storage to be made in 3/4" thick marine ply & the same to be finished in P.U. finish paint. Complete in all respect Including Hinges, Handle, Lock Etc. All Hardware shall be Haffale make.		13.50	sqm.		-
25	Removing & Refixing existing gas pipe as per plan/instructions including bracket back to normal.		75.00	Rmt.		-
26	Providing & Fixing facia over 7'-0" Ht. to be made in 3/4" ply in line of wall facia will be 1'-0" Ht. complete in all respect.		45.00	Rmt.		-
27	Providing & Fixing facia same as above Except facia will be 1'-0" in depth.		30.00	Rmt.		-
AA	Electrical Work					-
1	Supplying and fixing of 2/3/4 module switch box with modular plate including connections and all accessories as required. For below sockets , power points					-
1.1	Providing & Fixing 16 AMP switch /socket power plug point		15	Nos.		-
1.2	Providing & Fixing 6 AMP switch/socket Power plug point		15	Nos.		-
1.3	Providing & Fixing 6 AMP Switch with plate		45	Nos.		-

2	Supplying and fixing of RJ-11 modular telephone socket with G.I. switch box, modular plate including connections as required.		3	Nos.		-
3	Supplying and fixing following 3 module, GI box along with modular base & cover plate as required. Providing & Fixing RJ 45 Lan socket with terminations		9	Nos.		-
4	Supplying and drawing and end to end termination with all required accessories of UTP 4 pair CAT 6 LAN Cable in the existing surface/ recessed through PVC conduit as required.		300	Mtr		-
5	Providing & Fixing termination of point wiring for light point/ power points / LED strips / LED spot lights , with laying of 1.5 sqmm / 2.5 sq.mm FRLS PVC insulated copper conductor single core cable in surface / recessed medium class PVC conduit as per standard.		180	Nos.		-
6	Providing & Fixing of LED Strip with profile & Driver Lafeez make		105	Rmt.		-
7	Providing & Fixing Spot light Lafeez make		90	Nos.		-
					Total in Rs.	-
					SGST	-
					CGST	-
					<b>Total Cost inclusive of All Taxes and duties</b>	-

**NOTE:**

- 1 The agency is requested to visit the site to know actual scope of work.
- 2 Rate shall be quoted exclusive of GST which is to be mentioned at designated space above.
- 3 Material required at site should be assessed by the agency and bill will not be settled for excess/supplied items.
- 4 Bill will be settled as per actual measurement after supply of material at site.
- 5 Deviations/suggestions may be put on separate page in order to attain higher quality performance. Competent authority reserves full right to accept or reject any kind of changes.
- 6 Agency will have to prepare detailed plan of work & obtained approval before execution. Agency will have time bound work schedule for carrying out the work.
- 7 Payment will be released for actual work done on satisfactory completion on providing necessary certifications/documentation.
- 8 all above items of this schedule shall have standard make and approved to before installation.
- 9 Agency has to get a sample approved from Engineer-in-charge in writing before any supply of item.
- 10 ACTREC reserves the right to reject any sample and rescind the work order if the samples are found to be unsatisfactory and if the agency is unable to meet the requirement of ACTREC.